



DISTRICT PROJECT OFFICE, SAMAGRA SHIKSHA, MAYURBHANJ
Baripada, Pin-757002, Ph. No.-06792-260865, Fax-06792-260007

No: 1624 /CW/20. Date: 15/09/20

QUOTATION CALL NOTICE

Sealed quotations are invited from the intending Govt. approved laboratory/ farms and valid I.T. & GST registration certificate to conduct soil investigation for construction of 26 (Twenty Six) no's of KGBV Hostel building at Jharadihi Govt. UPS in Bahalda Block, Shyamsundarpur Govt. UPS in Bangriposi Block, Barasahi Govt. UPS in Barasahi Block, Maharani Takat Kumari Govt. UPS in Baripada Block, Dhanpur Nodal UPS in Betnoti Block, Purneswar Nodal UPS, Saragada in Bijatala Block, Bisoi Nodal High School in Bisoi Block, Khunta Govt. ME School in G.B. Nagar Block, Jamda Govt. UPS in Jamda Block, Durdura Nodal UPS in Jashipur Block, Kaptipada Govt. ME School in Kaptipada Block, Rasamtola Nodal UPS in Karanjia Block, Gayalmara Nodal UPS in Khunta Block, Chandua Govt. UPS in Kuliana Block, Chingudipokhari Nodal UPS in Kusumi Block, Bhaliadiha Govt. UPS in Morada Block, Gorumohisani Govt. ME School in Rairangpur Block, Binodray Govt. UPS in Rasgovindpur Block, Fulcomp Govt. UPS in Raruan Block, Paikabasa Govt. UPS in Samakhunta Block, Paktia Govt. UPS in Saraskana Block, Jamdapal Govt. UPS in Sukruli Block, Narayan Bidyapitha, Kantisahi in Suliapada Block, Thakurmunda Govt. UPS in Thakurmunda Block, Changua Govt. UPS in Tiring Block & Radho Govt. UPS in Udala Block of Mayurbhanj district through registered post / speed post only. The sealed quotations will be received at the District Project Office, Samagra Shiksha, Mayurbhanj up to **3:00 pm on 25.09.2020 and will be opened on 25.09.2020 at 4:00 pm** in the Office chamber of the undersigned. The details of the advertisement & schedule can be downloaded from the website of www.osepa.in & www.mayurbhanj.nic.in

Sd/-

**District Education Officer & DPC,
Samagra Shiksha, Mayurbhanj.**

SCHEDULE						
NAME OF THE WORK-SOIL INVESTIGATION FOR CONSTRUCTION OF 26 NOS OF UPGRADED KGBV HOSTEL BUILDING IN MAYURBHANJ DISTRICT.						
SI No	Description	Quantity	Unit	Rate in Rs. (Figure)	Rate in Rs. (Word)	Ramarks
1	Mobilisation of mechneries and trend personels to the site from destination To & Fro as per direciom of the Engineer-in-Charge at site.	26	Each			
2	Boring the soil Hard / Soft of 150mm dia and conducting SPT / DCPT and collecting UDS and DS at 1.5 mts interval or at the junction of change of layers as per direction of Engineer-in-Charge at site as mentioned in IS :- 1892-1979 up to a depth of 10 meters and above.	26	Rm			
3	Labortory testing of UDS / DS samples as per direction of the Engineer-in-Charge (15 nos of sites) as per physical requirement.	78	No			
i	Grain size analysis	78	No			
ii	Atterberg's limits (cone penetro meter)	78	No			
iii	Moisture content	78	No			
iv	Specific gravity	78	No			
v	Shear test including Bluk density	26	No			
vi	Diffrential Free Swell (DFS)	78	No			
4	Preparation of report recommending type of foundation along with SBC calculations in booklet form in triplicate as per direction of the Engineer-in-Charge (26 sites/ 78 booklet)	78	Sets			

- Note-** 1. The soil test should be conducted in the Govt. approved labortory / farms.
2. Payment will be made after submission of the bills in triplicate.
3. The selected farms to be execute the agreement with undersigned before issue of work order.
4. The undersigned reserves the rght to reject any or all the quotations without assigning any reason thereof.


District Education Officer & DPC,
Samagra Shiksha, Mayurbhanj.